


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 26/03/2018 upt 3.00 p.m. for the work of Providing & fixing LED street lights at gate no. 2 and providing & fixing tube & other fittings in passage & mid-landings of Bldg. No. SH-3 & SH-5 under S.R Scheme at Shed Complex, Dharavi, Mumbai.**
2. **The estimated cost of the work is Rs. 2,66,626.00** (Rupees Two Lakhs Sixty Six Thousand Six Hundred Twenty Six only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **14/03/2018 to 26/03/2018 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (Dharavi)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m.** by **26/03/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule ‘B’ are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days.**
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Dharavi)/SPPL as per the rules in force.


Executive Engineer (Dharavi),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(Dharavi)/ 287 /2018,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 14 / 03 / 2018

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to S.E./SPPL and D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : S.R Scheme at Shed Complex, Dharavi, Mumbai.

--- Providing & fixing LED street lights at gate no. 2 and providing & fixing tube & other fittings in passage & mid-landings of Bldg. No. SH-3 & SH-5.

: SCHEDULE 'B' :							
Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	Bd/A-1, P.259 (It.1, Pg.5, PWD DSR 2015-16)	9.00	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum including removing the excavated materials upto a distance of 50 meters beyond the building area and lift upto 1.50 metres, stacking and spreading as directed including dewatering unless provided elsewhere, preparing the bed for the foundation and necessary backfilling, ramming, watering comiete excluding shoring and strutting.	239.00	Rs. Two Hundred Thirty Nine only.	Cu.Mt.	2151.00
2	Bd/A-12, P.264 (It.10, Pg.7, PWD DSR 2015-16)	3.45	Providing dry trap / rubble stone soling 15cm to 20cm thick including hand packing and compacting etc. complete.	915.00	Rs. Nine Hundred Fifteen only.	Cu.Mt.	3156.75
3	Bd/E-1, P-287 (It.-1(d), Pg-13, PWD DSR 2015-16)	2.25	Providing and laying in position in situ plain cement concrete M-15 with minimum cement content of 320 Kg./Cum as per IS 456-2000 for accelerate, retard setting of concrete improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete.	6753.00	Rs. Six Thousand Seven Hundred Fifty Three only.	Cu.Mt.	15194.25
4	It. No. ME-10-5-d, Page 92, Mechanical & Electrical Dept. Schedule of Rate 2013.	1.00	Design, engineering, manufacture, testing at factory, packing & forwarding, delivery to site, unloading and handling at site, assembly, installation, testing and commissioning of Octagonal street light poles with embeded junction box inclusive of terminals, 3Cx 2.5 sqmm PVC insulated multistranded flexible copper cable from Junction box to the luminaires, termination at both ends and other accessories. Foundation for the 6 mtr. pole erection and all civil works shall be in the scope of the contractor.	23357.00	Rs. Twenty Three Thousand Three Hundred Fifty Seven only.	Each	23357.00
5	It. No. ME-10-6-b, Page 92, Mechanical & Electrical Dept. Schedule of Rate 2013.	1.00	Hot Dip Galvanised Octoganal poles brackets for street lighting : Double arm bracket 1000mm long for 3m to 10m poles.	3727.00	Rs. Three Thousand Seven hundred Twenty Seven only.	Each	3727.00

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
6	It. No. ME-16-9-o, Page 116, Mechanical & Electrical Dept. Schedule of Rate 2013.	25.00	UPVC. Pipe.ISI marked - IS 4985 110 mm. 6 kgf.	346.00	Rs. Three Hundred Forty Six only.	Mtr.	8650.00
7	It. No. 38, Bd/V-43, P-574, Page 136 (PWD DSR 2015-16)	2.00	Providing and constructing Brick Masonry Inspection Chamber 60 cm x 45 cm and 45 cm to 90 cm in depth including necessary excavation, cement concrete 1:4:8 foundation, cement concrete 1:2:4, 23 cm thick channels, brick masonry, plastering from inside and outside as required in cement mortar 1:3 and airtight cast iron heavy type lid (1 CWT weight) with frame fixed in cement concrete 1:2:4 etc. complete as directed.	9502.00	Rs. Nine Thousand Five Hundred Two only.	Nos.	19004.00
8	(It. No. FMB 11.63 page B-54 of MCGM FMR)	0.006	Providing and fixing in position light weight M.S. Angles, tees, plates, rolled steel beams, joist and stanchions etc. including all labour and material in hoisting, fixing with bolts and nuts or by welding etc. complete including 3 coats of syn. Ena. paints (steel to be supplied by Municipal Corporation)	86568.00	Rs. Eighty Six Thousand Five Hundred Sixty Eight only.	M.T.	519.41
9	It. No. 2-9-3, Page 56 (PWD Electrical DSR 2013-14)	2.00	Supplying and erecting approved type LED street light fitting above 24 to 36W, having PF > 0.95, class IP 65 or above. Housing of pressure die cast aluminium alloy and heat sink extruded aluminium as per specification no. FG-ODF/FLS2	10755.00	Rs. Ten Thousand Seven Hundred Fifty Five only.	Each	21510.00
10	It. No. 7-2-2, Page 110 (PWD Electrical DSR 2013-14)	76.00	Supplying & erecting PVC armoured cable 2 core 4 sq mm copper conductor continuous 5.48 sq mm (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/CU.	189.00	Rs. One Hundred Eighty Nine only.	Meter	14364.00
11	It. No. 7-2-9, Page 111 (PWD Electrical DSR 2013-14)	6.00	Supplying, erecting & terminating PVC armoured cable 4 core 4 sq mm copper conductor continuous 5.48 sq mm (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/CU	296.00	Rs. Two Hundred Ninety Six only.	Meter	1776.00
12	It. No. 5-1-7, Page 77 (PWD Electrical DSR 2013-14)	1.00	Supplying and erecting Triple pole metal/ iron clad switch and fuse 415/500V 63A on angle iron frame as per specification No. SW-SWR/MTP	2773.00	Rs. Two Thousand Seven Hundred Seventy Three only	Each	2773.00

Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
13	It. No. 7-8-2, Page 119 (PWD Electrical DSR 2013-14)	2.00	Supplying & erecting water tight terminal box of 1.6 mm (16 gauge) CRCA sheet of size 200 x 150 x 150 mm. complete on pole as per specification No. CB-SB	493.00	Rs. Four Hundred Ninety Three only	Each	986.00
14	It. No. ME-7-1-c, Page 73, Mechanical & Electrical Dept. Schedule of Rate 2013.	1.00	Earthing station with 600 mm x 600 mm x 6 mm galvanised iron plate & 50 mm dia. G.I. pipe, 3000mm long GI pipe (Class B or better) earth pit as per IS 3043. The earth pit shall be provided with watering pipe (Class B) with wire messed funnel, 25x3 GI strip / 8 SWG GI wire up to chamber (wire or strip size as per fault level), disconnecting links with 600 x 600 mm (clear) RCC chamber & heavy duty 3mm thick CI chequered plate cover with hinge & stainless steel bolts. C25Bentonite/ Charcol & Salt shall be provided for earth pits. Excavation, backfilling, removal of excess soil is included in the scope.	10000.00	Rs. Ten Thousand only.	No.	10000.00
15	It. No. 1-6-4, Page 19 (PWD Electrical DSR 2013-14)	364.00	Supplying & erecting mains with 2x2.5 sq.mm.and earth wire, 1.5 sq.mm FRLS PVC copper wire in rigid PVC conduit min.20mm dia. as per specification No: WG-MA/PC, para no. 1.4.1	129.00	Rs. One hundred Twenty Nine only.	Meter	46956.00
16	ME-3-6-a, Pg.32, (MCGM's Mech. & Elect.Schedule 2013)	56.00	Point wiring by using PVC insulated copper conductors (alongwith same size of pvc insulated copper conductor for earthing & 3 plate ceiling rose) using CASING-N CAPING. For Light/Fan / Ex. Fan Points.	729.00	Rs. Seven Hundred Twenty Nine only.	Each Point	40824.00
17	It. No. 2-4-9, Page 45 (PWD Electrical DSR 2013-14)	40.00	Supplying and erecting approved make white stove enamelled / powder coated CRCA sheet not less than 0.7 mm thick chalk board type fluo.fitting of 1 xT8 36/40 W.with 40 W Electronic Ballast having pf > 0.90 fixed at ceiling or on wall as per specification no. FGIDF/ CBF	907.00	Rs. Nine Hundred Seven only.	Each	36280.00
18	It. No. 5-3-11, Page 82 (PWD Electrical DSR 2013-14)	18.00	Supplying, erecting & marking SPN MCB 6A to 32A, B- series (for lighting) in provided distribution board as per specification No. SW-SWR/MCB	433.00	Rs. Four Hundred Thirty Three only.	Each	7794.00
19	It. No. 5-6-15, Page 88 (PWD Electrical DSR 2013-14)	9.00	Supplying & fixing CRCA sheet Box with earthing terminals for housing 2 Pole RCCB/RCCB+MCB complete on iron frame/laminated board.	201.00	Rs. Two Hundred one only.	Each	1809.00
20	It. No. 2-1-10, Page 39 (PWD Electrical DSR 2013-14)	16.00	Supplying and erecting T8 Fluorescent tube day light 1200mm 36 W	57.00	Rs. Fifty Seven only.	Each	912.00
21	(It.16, Pg.39, PWD DSR 2015-16)	5.70	Removing any kind of debris including loading in truck and conveying to dumping point approved by BMC, unloading, spreading etc. complete. With all leads and lifts.	690.00	Rs. Six hundred ninety only.	Cu.Mt.	3933.00


Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
22	(It.60(b), Pg.161, PWD DSR 2015-16)	10.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rs. Ninety Five only.	03 Copies each photo	950.00
Total Rs.							266,626.41
Say Rs.							266,626.00

(Rupees Two Lakhs Sixty Six Thousand Six Hundred Twenty Six only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


 Executive Engineer (Dharavi)/SPPL