


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 19/07/2018 upt 3.00 p.m. for the work of providing & fixing Orissa type W.C. pan, white glazed tiled flooring & dado, providing & fixing UPVC door frame & shutters to W.C. for Ladies & Gent's toilet for shops in Rehab Building no. 6 under S.R Scheme at Rahul Nagar, Sewri, Mumbai.**
2. **The estimated cost of the work is Rs. 1,15,617.00** (Rupees One Lakh Fifteen Thousand Six Hundred Seventeen only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (City), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **13/07/2018 to 19/07/2018 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (City)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m. by 19/07/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (City)/SPPL as per the rules in force.


Executive Engineer (City),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(City)/818/2018,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 13 / 07 / 2018

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : S.R Scheme at Rahul Nagar, Sewri, Mumbai.

--- Providing & fixing orissa type W.C. pan, white glazed tiled flooring & dado, providing & fixing UPVC door frame & shutters to W.C. for Ladies & Gent's toilet for shops in Rehab Building no. 6.

: SCHEDULE 'B' :							
Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	Bd/W-8, P-587 (It.67, Pg.141 PWD DSR 15-16)	2.00	Removing W.C. pans including disconnecting the sanitary and water supply connections, removing and breaking flooring and bed concrete around pans and removing pan carefully and throwing our the refusal outside etc. complete.	131.00	Rupees One Hundred Thirty One only.	No.	262.00
2	CS-DD-19-a. Pg.164. (MCGM's Buildings Schedule/Common Schedule 2013)	7.17	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	27.00	Rupees Twenty Seven only.	Sq.Mt.	193.59
3	CS-DD-65, Pg.167, (MCGM's Buildings Schedule/Common Schedule 2013)	51.17	Removing cement plaster of any finish from the wall, complete with racking out the joints to a depth of 20 mm.	87.00	Rupees Eighty Seven only.	Sq.Mt.	4451.79
4	(It.-7, Pg-36, PWD DSR 2015-16)	0.72	Providing waterproofing in W.C. and bath including brick bat coba in all positions consisting of specialised materials as per manufacturer's specifications and covering ten years' guarantee on requisite stamp paper including all leads, lifts and curing etc. complete.	4727.00	Rupees Four Thousand Seven Hundred Twenty Seven only.	Cu.Mt.	3403.44

Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
5	(It.No 8, Pg.36) of PWD DSR 2015-16	1.80	Providing waterproof bedding 25 mm thick for flooring of bath and W.C. in cement mortar 1:3 using 1 kg of waterproofing compound of approved make and manufacture per bag of cement including leveling, curing, etc. complete.	484.00	Rupees Four Hundred Eighty Four only.	Sq.Mt.	871.20
6	It.No 6, Pg.36) of PWD DSR 2015-16	18.14	Providing waterproof plaster in W.C. and bath 20 mm thick for dado in cement mortar 1:3 with neat finishing, floating using waterproofing compound at the rate of One kg. per bag of cement, etc. complete	381.00	Rupees Three Hundred Eighty One only.	Sq.mt.	6911.34
7	Bd/L-2, P-368 (It.-2(a), Pg-53, PWD DSR 2015-16)	33.03	Providing internal cement plaster 12 mm thick in a single coat in in cement mortar 1:3 without neeru finish to concrete or brick surfaces in all positions including scaffolding and curing complete.	221.00	Rupees Two Hundred Twenty One only.	Sq.Mt.	7299.63
8	Bd/L-10, P-360 (It.-8, Pg-54, PWD DSR 2015-16)	33.03	Providing neeru finish to plastered surfaces in all position including scaffolding and curing complete.	55.00	Rupees Fifty five only.	Sq.Mt.	1816.65
9	Bd/V-20, P-559 (It.-18(a), Pg-129, PWD DSR 2015-16)	2.00	Providing and fixing Orissa type white glazed earthenware 580 mm x 450 mm water closet pan including trap cast iron soil and vent pipes upto the outside face of the wall including 100 mm. Diameter cast iron plug bend, cement concrete bedding, 10 litres capacity H.D.P.E. flushing cistern with fittings, inlet pipe with stop tap, brackets, 32 mm. diameter galvanised iron heavy type flush pipe with fittings and clamps, painting in gray oil paint to the exposed pipes and cutting and making good the walls and floors etc. complete (Excluding waterproof brick bat coba)	8038.00	Rupees Eight Thousand Thirty Eight only.	No.	16076.00
10	Bd/M-12, P-385 (It.-11(a), Pg-59, PWD DSR 2015-16)	1.80	Providing and laying white glazed tile 200 x 100 mm in size and 8 to 9.5 mm thick for flooring in required positions laid on a bed of 1:4 cement mortar including neat cement float, all special required like round, edge tiles, corner cups, etc. filling joints with white cement slurry, curing and cleaning complete.	1183.00	Rupees One Thousand One Hundred Eighty Three only.	Sq.Mt.	2129.40

Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
11	Bd/M-13 P-386 (It.-12(a), Pg-59, PWD DSR 2015-16)	27.69	Providing and fixing white glazed tile of 200 x 100 mm in size and about 6.5 mm thick for dado and skirting in required positions fixed on plaster of cement mortar 1:4 including neat cement float, all special required like round, edge tiles, corner cups etc. filling joints with neat cement slurry mixed with approved shade of pigment to match the colour of tiles, curing and cleaning etc. complete.	1278.00	Rupees One Thousand Two Hundred Seventy Eight only.	Sq.Mt.	35387.82
12	Bd/M-3, P-380 (It.3(c), Pg.57 PWD DSR 15-16)	3.45	Providing and laying polished Kotah Stone flooring of approved quality 25 mm to 30 mm thick and having size not less than 55 cm in plain/diamond pattern laid on a bed of cement mortar 1:6 including cement float, filling joints with neat cement slurry, curing, polishing and cleaning complete.	969.00	Rupees Nine Hundred Sixty Nine only.	Sq.Mt.	3343.05
13	Bd/V-5 P-551 (It.-2(a), Pg-124, PWD DSR 2015-16)	3.00	Providing and fixing G.I. Pipes 15 mm diameter heavy type having 21.3 mm outer diameter and 1.504 kilogramme per metre weight and having embossed at every metre as ISI mark and name of the manufacturer to walls, ceilings, floors etc. with screwed sockets, backnuts, elbows, tees, reducers, enlargers, plugs, clamps etc. including necessary drilling in holes in walls/slabs etc. and remaking good the demolished portion to restore the same in original condition neatly and applying primer and two coats of white oil painting including existing pipe, if necessary & conveying & stacking the same in P.W.D. chowky or as directed etc. complete.	313.00	Rupees Three Hundred Thirteen only.	R.Mt.	939.00
14	Bd/V-8 (It.5, Pg.126, PWD DSR 2015-16)	2.00	Providing & fixing heavy type 12 mm dia. Screw down bib/stop tap of brass including socket, union nut, etc. complete.	418.00	Rupees Four Hundred Eighteen only.	No.	836.00
15	Bd/V-30 (It.23(a), Pg.131, PWD DSR 2015-16)	1.00	Providing and fixing white glazed earthenware wash hand basin of 55 cm x 40 cm size including one cold water pillar tap, brackets, rubber plugs and brass chain, stop tap and necessary pipe connection including bottle trap and polyethylene waste water pipe upto the out side face of the wall, making good the damaged surface, testing etc. complete.	4345.00	Rupees Four Thousand Three Hundred Forty Five only.	Each	4345.00

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
16	CS-PN-3, Pg 48 (MCGM's Buildings Schedule/Common Schedule 2013)	33.03	Providing and applying first single coat of approved primer and two coats of acrylic distemper (oil bound distemper) of an approved make and colour as per manufacturers specifications to any surface, at all height and locations as directed including scaffolding, cleaning and preparing surfaces for painting with broom by any approved means, etc. complete as directed by Engineer-in-charge.	94.00	Rupees Ninety Four only.	Sq.Mt.	3104.82
17	CS-DD-8-b, Page 163 (MCGM's Common Schedule 2013)	6.00	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area beyond 3 sq. metres.	191.00	Rupees One Hundred Ninety one only.	Each	1146.00
18	(It.54, Pg.101, PWD DSR 15-16)	2.70	Providing and fixing aluminium louvered windows consisting of vertical arm Metre (40x12mm) with holders, lever and locking arrangement wasting at 0.91 Kg/M with 3mm thick sheet glass louvers etc complete. Spec: (As directed by Engineer in-charge)	2476.00	Rupees Two Thousand Four Hundred Seventy Six only.	Sq.mt.	6685.20
19	It.No.103, Pg.115 of PWD DSR 2015-16	9.00	Providing and fixing prefabricated UPVC Door frame for door size 1.98 x 0.91 mtr. Along with all accessories like stainless steel screws, using 50 mm x 50 mm x 2.5 mm UPVC section. The UPVC frame section will be reinforced with G.I.C. channel. (excluding frame). Etc. complete.	441.00	Rupees Four Hundred Forty One only.	R.Mt.	3969.00
20	It.No.102, Pg.115 of PWD DSR 2015-16	2.59	Providing and fixing UPVC Door of size 1.98 m X 0.91 m or of read size and colour along with all accessories like Hinges, Tower Bolts, Aldrop, Screw, Handel, tadi, etc. hollow section of size 150 mm x 31 mm x 1.2 mm UPVC profile with bordar of "U" hollow size section of size 35mm x 35mm x 2mm the corner will be joined with tough plastic of "L" angles at all corners with stainless steel screws etc. complete.	3657.00	Rupees Three Thousand Six Hundred Fifty Seven only.	Sq.Mt.	9471.63
21	(It.-35, Pg-65, PWD DSR 2015-16)	5.66	Washing and cleaning any kind of tiled flooring, dado with washing powder and water.	13.85	Rupees Thirteen point Eighty Five only.	Sq.Mt.	78.39
22	(It.16, Pg.39, PWD DSR 2015-16)	2.82	Removing any kind of debris including loading in truck and conveying to dumping point approved by BMC, unloading, spreading etc. complete. With all leads and lifts.	690.00	Rupees Six Hundred ninety only	Cu Mt.	1945.80


Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
23	(It.60(b), Pg.161, PWD DSR 2015-16)	10 00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rupees Ninety five only.	03 Copies each photo	950.00
						Total Rs.	115,616.75
						Say Rs.	115,617.00

(Rupees One Lakh Fifteen Thousand Six Hundred Seventeen only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


 Executive Engineer (City)/SPPL