


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 24/09/2018 upt 3.00 p.m. for the work of Supplying & erecting mains with 2 x 2.5 sq.mm. and 1x1.5 sqmm earth copper insulated wire, providing & fixing 40 Amp 2 pole RCCBs, supplying & fixing CRCA Sheet Box for tenements at Fourth floor to Seventh floor under S.R. Scheme on plot bearing C.S. No. 181 (pt), 189 (pt), 190 (pt) of Dharavi Division at G/North, Mumbai - 17.**
2. **The estimated cost of the work is Rs. 2,94,491.00** (Rupees Two Lakhs Ninety Four Thousand Four Hundred Ninety One only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **17/09/2018 to 24/09/2018 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (Dharavi)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai 400 051 upto **3.00 p.m.** by **24/09/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 30 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **60 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Dharavi)/SPPL as per the rules in force.


Executive Engineer (Dharavi),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(Dharavi)/114/2018,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E).
Mumbai- 400 051.

Date : 17 / 09 / 2018

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to S.E./SPPL, D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

Name of Work: S.R. Scheme on plot bearing C.S. No. 181 (pt), 189 (pt), 190 (pt) of Dharavi Division at G/North, Mumbai - 17.
 --- Supplying & erecting mains with 2 x 2.5 sq.mm. and 1x1.5 sqmm earth copper insulated wire, providing & fixing 40 Amp 2 pole RCCBs, supplying & fixing CRCA Sheet Box for tenements at Fourth floor to Seventh floor.

: SCHEDULE 'B' :							
Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	It. No. 1-15-3, Page 45 (PWD Electrical DSR 2017-18)	704.00	Dismantling the existing Aluminium/copper mains, sub-mains wiring upto 10 sq.mm. along with accessories etc. complete as per specification No. WG-DM/PW. <i>Note - Dismantled material of Point wiring / circuit mains/mains, sub-mains / telephon / LAN / WAN / TV wires / cables shall be retained by contractor.</i>	3.00	Rupees Three only.	Mtr.	2112.00
2	It. No. 5-12-2, Page 123 (PWD Electrical DSR 2017-18)	64.00	Making the site clear of dismantled DB and switch gears by refilling the holes with cement mortar & finishing in an approved manner	66.00	Rupees Sixty Six only.	Each	4224.00
3	It. No. 5-6-2, Page 111 (PWD Electrical DSR 2017-18)	64.00	Providing, erecting & commissioning RCCB only of electro magnetic typw with 30/100/300 mA sensitivity and having capacity of 40A 2 pole complete as per specification No. SW-RCCB/RCCB.	2435.00	Rupees Two Thousand Four Hundred Thirty Five only.	Each	155840.00
4	It. No. 1-6-4, Page 22 (PWD Electrical DSR 2017-18)	704.00	Supplying & erecting mains with 2x2.5 sq.mm. and earth wire 1.5 sq.mm FRLS PVC copper wire in rigid PVC conduit min. 20mm dia. as per specification No. WG-MA/PC, para no. 1.4.1.	153.00	Rupees One Hundred Fifty Three only.	Meter	107712.00
5	It. No. 5-6-15, Page 112 (PWD Electrical DSR 2017-18)	64.00	Supplying & fixing CRCA sheet Box with earthing terminals for housing 2 Pole RCCB complete on iron frame/laminated board.	226.00	Rupees Two Hunderd Twenty Six only.	Each	14464.00
6	It. No. 7-9-1, Page 160 (PWD Electrical DSR 2017-18)	64.00	Supplying & erecting crimping type copper lugs for cable upto 16 sq mm complete as per specification No. CB-CL/CU	18.00	Rupees Eighteen only.	Each	1152.00
7	It. No. 1-2-24, Page 14 (PWD Electrical DSR 2017-18)	128.00	Supplying & erecting UPVC gland/ adaptor suitable for 20 mm dia pvc pipe.	17.00	Rupees Seventeen only.	Each	2176.00

Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
8	It. No. 1-3-6. Page 16 (PWD Electrical DSR 2017-18)	96.00	Supplying & erecting mains with 2x2.5 sq.mm F.R.L.S copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places. as per specification No: WG-MA/BW	66.00	Rupees Sixty Six only.	Meter	6336.00
9	(It.60(b), Pg.161, PWD DSR 2015-16)	5.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rupees Ninety Five only.	03 Copies each photo	475.00
Total Rs.							294,491.00
Say Rs.							294,491.00

(Rupees Two Lakhs Ninety Four Thousand Four Hundred Ninety One only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


 Executive Engineer (Dharavi)/SPPL