


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 28/09/2018 upt 3.00 p.m. for the work of Rectification / replacement of damaged civil, plumbing work in 6 rooms on 3rd floor in building no. SH-3 under S.R Scheme at Shed Complex, Dharavi, Mumbai.**
2. **The estimated cost of the work is Rs. 2,02,321.00** (Rupees Two Lakhs Two Thousand Three Hundred Twenty One only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **21/09/2018** to **28/09/2018** upto **2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (Dharavi)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m.** by **28/09/2018** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 30 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **60 days.**
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.
13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.

14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Dharavi)/SPPL as per the rules in force.


Executive Engineer (Dharavi),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(Dharavi)/1126/2018,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 21 / 09 / 2018

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to S.E./SPPL, D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

Name of work - S.R Scheme at Shed Complex, Dharavi, Mumbai.

--- Rectification / replacement of damaged civil, plumbing work in 6 rooms on 3rd floor in building no. SH-3.

: SCHEDULE 'B' :							
Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	Bd/V-8 (It.5, Pg.126, PWD DSR 2015-16)	18.00	Providing & fixing heavy type 12 mm dia. Screw down bib/stop tap of brass including socket, union nut, etc. complete.	418.00	Rs. Four Hundred Eighteen only.	No.	7524.00
2	(It.51, Pg.99, PWD DSR 2015-16)	6.48	Providing and fixing in position extruded modular alluminium section Three Track Sliding Window without powder coating made up of three track drain bottom section of size 92mm x 45mm x 1.05mm thick (1.659 Kg/Rmt) three track top and sides sections of size 92mm x 31mm x 1.3mm thick (0.933 Kg/Rmt). The shutter should be bearing bottom of size 40mm x 18mm x 1.25mm thick (0.417 Kg/Rmt) Interlocking section size of 40mm x 18mm x 1.10 mm thick (0.469 Kg/Rmt) handles section of Size 40mm x 18mm x 1.25mm thick (0.417 Kg/Rmt) with 5.5 mm thick selected quality tinted glass in shutter with approved quality neoprene, gasket P.V.C. lining etc. complete (Excluding frame).	4985.00	Rs. Four Thousand Nine Hundred Eighty Five only.	Sq.Mt.	32302.80
3	(It.50, Pg.99, PWD DSR 2015-16)	4.32	Providing and fixing in position extruded modular alluminium section Two Track Sliding Window without powder coating made up of two track drain bottom section of size 61mm x 45mm x 1.3mm thick (1.055 Kg/Rmt) and top and side sections of size 61mm x 31mm x 1.3mm thick (0.659 Kg/Rmt). The shutter should be bearing bottom of size 40mm x 18mm x 1.2mm thick (0.417 Kg/Rmt) top member of size 40 mm x 18 mm x 1.20 mm Thick (0.475 Kg/Rmt) Interlocking section size of 43mm x 27mm x 1.30 mm thick (0.558 Kg/Rmt) and handle section of size 43mm x 18mm x 1.30 mm thick (0.424 Kg/Rmt) selected quality 5.5 mm thick tinted glass to be fixed in shutter with neoprene, gasket with approved quality P.V.C. rollers, necessary locks handles, P.V.C. lining etc. complete (Excluding frame).	4567.00	Rs. Four thousand five hundred sixty seven only.	Sq.Mt.	19729.44
4	(It.54, Pg.101, PWD DSR 15-16)	3.24	Providing and fixing aluminium louvered windows consisting of vertical arm Metre (40x12mm) with holders, lever and locking arrangement wasting at 0.91 Kg/M with 3mm thick sheet glass louvers etc complete. Spec: (As directed by Engineer in-charge)	2476.00	Rs. Two thousand four hundred seventy six only.	Sq.mt.	8022.24

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
5	Bd/V-30, P-565 (It.23(a), Pg.131 PWD DSR 15-16)	6.00	Providing and fixing white glazed earthenware wash hand basin of 55cm x 40cm size including one cold water pillar tap, brackets, rubber plugs and brass chain, stop tap and necessary pipe connection including bottle trap and polythylene waste water pipe upto the out side face of the wall, making good the damaged surface, testing etc. complete.	4345.00	Rs. Four Thousand Three Hundred Fourty five only.	Nos	26070.00
6	R2-CS-PS-136-a-1, Pg.153, (MCGM's Buildings Schedule/Commo n Schedule 2018)	12.00	Providing and fixing PTMT grating of approved quality and colour Circular type 100 mm nominal dia.	54.00	Rs. Fifty Four only.	No.	648.00
7	R2-CS-DD-65, Pg.187, (MCGM's Buildings Schedule/Commo n Schedule 2018)	16.84	Removing cement plaster of any finish from the wall, complete with racking out the joints to a depth of 20 mm.	147.00	Rs. One Hundred fourty seven only.	Sq.Mt.	2475.48
8	R2-CS-PL-05, Pg.34, (MCGM's Buildings Schedule/Commo n Schedule 2018)	16.84	Providing and applying 12 mm thick internal plaster in cement mortar 1:3 with neeru finish at all heights and locations in one coat for masonry (except stone masonry) and concrete surfaces including racking out joints, hacking of concrete surface, watering, finishing, curing, scaffolding etc. complete.	361.00	Rs. Three Hundred sixty one only.	Sq.Mt.	6079.24
9	R2-CS-DD-71, Pg.187, (MCGM's Buildings Schedule/Commo n Schedule 2018)	5.00	Removing existing door or windows with frame and shutters and making good etc. to the existing surface.	563.00	Rs. Five Hundred Sixty three only.	Nos.	2815.00
10	R2-CS-WW-06-c, Page 104 of MCGM's Building Schedule/Commo n Schedule 2018	9.45	Providing and fixing superior quality single leaf B.W.P. grade solid core flush door 35mm thick shutter shutters of standard make conforming to IS:2202- 1991 (Part I & II) including one coat of primer, putty and 2 coats of synthetic enamel paint on both faces etc. with 12 mm thk teak wood lipping all around all around etc. complete (Hinges, aldrep & standard door hardware to be paid separately)	2131.00	Rs. Two thousand one hundred thirty one only.	Sq.Mt.	20137.95

Item. No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
11	R. A. adopted for rectification work in Dindoshi Bldg. No.19	5.00	Providing, making and fixing Mild Steel frame out of 1.25mm thick sheet conforming to I.S. 513/ 1079 of sizes as detailed under profile to be single 32 x 14mm rebated, frame shall be received in knock down or selded condition, frames, stiffened and prepared with protective guard boxes to receive hinges, lock plated, shock absorbed tower bolts etc. Also include two coats of zinc rich T.I. etched primer. Frames shall be complete with 3 Nos. 50 x 225mm long and 2m thick G.I. holdfast on each side, filled in cement concrete 1:3:6, 230 x 230 x 200mm tie rod at bottom, corner etc. Hollow frame fully grouted with cement concrete minimum (1:3:6) etc. all complete as per detailed in drawing and approved by Engineer	2082.00	Rs. Two thousand eighty two only.	Nos.	10410.00
12	R2-CS-PN-26, Pg. 193 of MCGM's Buildings Schedule / Common	12.15	Providing and applying synthetic enamel paint or flat oil paint in any required shade in 3 coats over a primer coat as per manufacturers specifications including scrapping, cleaning the surface etc. Complete.	200.00	Rs. Two hundred only.	Sq.mt.	2430.00
13	R2-CS-HW-04, Page 117 of MCGM's Building Schedule/Common Schedule 2018	5.00	Providing and fixing butt hinges 100 mm Long, manufactured as per relevant IS for door & windows with necessary materials and labour costs etc. complete.	134.00	Rs. One hundred thirty four only.	Nos.	670.00
14	R2-CS-HW-06-c-2, Page 119 of MCGM's Building Schedule/Common Schedule 2018	5.00	Providing and fixing aldrops of 16 mm diameter bars 300 mm long manufactured as per IS:2681-1991, wherever they apply for doors and windows with necessary materials and labour etc. complete.	398.00	Rs. Three Hundred Ninety Eight only.	Nos.	1990.00
15	R2-CS-HW-08-b-2, Page 120 of MCGM's Building Schedule/Common Schedule 2018	5.00	Providing and fixing tower bolts 150 mm long as described below conforming to IS:204- 1992 (Part I,II) for doors & windows with necessary materials and labour etc. complete.	90.00	Rs. Ninety only.	Nos.	450.00
16	R2-CS-HW-03-a, Page 117 of MCGM's Building Schedule/Common Schedule 2018	5.00	Providing and fixing door stopper Anodized Aluminium door stopper of approved make manufactured as described below and as per IS:1823- 1992 for doors with necessary materials and labour cost etc. complete.	82.00	Rs. Eighty two only.	Nos.	410.00

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
17	R2-CS-HW-09-c-1, Page 121 of MCGM's Building Schedule/Common Schedule 2018	5.00	Providing and fixing handles 100 mm long as described below, manufactured as per IS:208-1992 for doors and windows and with necessary materials and fixtures like screws etc. and all labour etc. complete.	79.00	Rs. Seventy Nine only.	Nos.	395.00
18	It.No.35, Pg.65 of PWD DSR 2015-16	219.72	Washing and cleaning any kind of tiled flooring, dado with washing powder and water.	13.85	Rs. Thirteen point eighty five only.	Sq.Mt.	3043.12
19	R2-CS-RM-34, Pg. 168, (MCGM's Buildings Schedule/Common Schedule 2018)	516.00	Removing white wash or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	11.00	Rs. Eleven only.	Sq.Mt.	5676.00
20	R2-CS-PN-3, Pg.56, (MCGM's Buildings Schedule/Common Schedule 2018)	516.00	Providing and applying first single coat of approved primer and two coats of acrylic distemper (oil bound distemper) of an approved make and colour as per manufacturers specifications to any surface, at all height and locations as directed including scaffolding, cleaning and preparing surfaces for painting with broom by any approved means, etc. complete as directed by Engineer-in-charge.	98.00	Rs. Ninety Eight only.	Sq.Mt.	50568.00
21	(It.60(b), Pg.161, PWD DSR 2015-16)	5.00	Shooting of still photographs outdoor and indoor of construction and other works of building, bridges, roads, etc. in district and outside district at any distance. (Still Photo 4" x 6" size)	95.00	Rs. Ninety Five only.	03 Copies each photo	475.00
						Total Rs.	202,321.27
						Say Rs.	202,321.00

(Rupees Two Lakhs Two Thousand Three Hundred Twenty One only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s


Executive Engineer (Dharavi)/SPPL