

Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 28/03/2016 upt 3.00 p.m. for the work of Providing plaster, white wash and cement concrete flooring in lift machine rooms of Bldg. no. SH-1, SH-3, SH-5 & SH-6 under S.R. Scheme at SHED Complex, Dharavi, Mumbai.**
2. **The estimated cost of the work is Rs. 2,20,243.00** (Rupees Two Lakhs Twenty Thousand Two Hundred Forty Three only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (Dharavi), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **14/03/2016 to 28/03/2016 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (Dharavi)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m.** by **28/03/2016** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 180 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (Dharavi)/SPPL as per the rules in force.

Executive Engineer (Dharavi),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(Dharavi)/ 312 /2016,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 11 / 03 / 2016

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to S.E.(Dharavi)/SPPL for information & necessary action

Copy to Notice Board/SPPL.

Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website.

NAME OF WORK : S.R. Scheme at SHED Complex, Dharavi, Mumbai.

--- Providing plaster, white wash and cement concrete flooring in lift machine rooms of Bldg. no. SH-1, SH-3, SH-5 & SH-6 .

: SCHEDULE 'B' :

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
1	Bd/M-6, P-381 (It.-7(a), Pg-72, PWD DSR 2014-15)	143.80	Providing and laying cement concrete flooring 40 mm thick with M-20 cement concrete laid to proper line level and slope in alternate bays including compaction, filling joints, marking lines to give the appearance of tiles of 30 cm x 30 cm or other size, as specified and laid diagonally or square, finishing smooth (with extra cement) in any colour as directed, and curing complete.	380.45	Rupees three hundred eighty point forty five only.	Sq.Mt.	54706.88
2	CS-SS-29, Page 80 of MCGM's Building Schedule/Common Schedule 2013	4.00	Providing & fixing G. I. corrugated sheet door of size 0.76 m. x 1.9 m. with G. I. sheet shutter of 22 gauge and G. I. sheet box frame of 18 gauge filled with 1 : 2 : 4 cc. including all fixtures i. e. aldrops, tadi, tower bolt, hold fast, handle, hinges including painting etc. complete as directed.	3000.00	Rupees three thousand only.	Each	12000.00
3	CS-DD-65, Pg.167, (MCGM's Buildings Schedule/Common Schedule 2013)	233.08	Removing cement plaster of any finish from the wall, complete with racking out the joints to a depth of 20 mm.	87.00	Rupees eighty seven only.	Sq.Mt.	20278.10
4	Bd/L-2, P-368 (It.-2(b), Pg-67, PWD DSR 2014-15)	233.08	Providing internal cement plaster 12 mm thick in a single coat in in cement mortar 1:4 without neeru finish to concrete or brick surfaces in all positions including scaffolding and curing complete.	221.15	Rupees two hundred twenty one point fifteen only.	Sq.Mt.	51546.00
5	CS-RM-34, Pg. 156, (MCGM's Buildings Schedule/Common Schedule 2013)	1176.30	Removing white wash or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	7.00	Rupees seven only.	Sq.Mt.	8234.10
6	As per wording of Item (Rate Analysis)	1409.38	Providing and applying 3 coats of white/colour wash etc. complete.	40.00	Rupees forty only.	Sq.Mt.	56375.26
7	Bd/L-10, P-370 (It.-8, Pg-68, PWD DSR 2014-15)	233.08	Providing neeru finish to plastered surfaces in all position including scaffolding and curing complete.	54.95	Rupees fifty four point ninety five only.	Sq.Mt.	12807.83

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
8	(It.-11, Pg-51, PWD DSR 2014-15)	3.50	Lowering down the debris obtained from breaking and removing the cement plaster / burnt brick masonry including removing tiles / kitchen otta of the first floor by any means without causing dust nuisance and damage to structure, stacking the same as and where directed including cleaning the site complete.	538.40	Rupees five hundred thirty eight point forty only.	Cu.Mt.	1882.37
9	(It.16, Pg.53, PWD DSR 2014-15)	3.50	Removing any kind of debris including loading in truck and conveying to dumping point approved by BMC, unloading, spreading etc. complete. With all leads and lifts.	690.00	Rupees six hundred ninety only.	Cu.Mt.	2412.39
Total Rs.							220,242.94
Say Rs.							220,243.00

(Rupees Two Lakhs twenty thousand two hundred forty three only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s

Executive Engineer (Dharavi)/SPPL