


Shivshahi Punarvasan Prakalp Ltd.

5th Floor, Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051.

QUOTATION NOTICE

1. Quotations in sealed covers are invited from the Contractors so as to reach the office of the undersigned at Shivshahi Punarvasan Prakalp Ltd. Griha Nirman Bhavan, Bandra (E), Mumbai- 400 051 **on or before 12/08/2016 upt 3.00 p.m. for the work of Preparation of ground for raising lawn, plantation of grass and maintenance of garden (RG1) & RG2(pt) under S.R Scheme at Rahul Nagar, Sewri, Mumbai.**
2. **The estimated cost of the work is Rs. 2,87,681.00** (Rupees Two Lakhs Eighty Seven Thousand Six Hundred Eighty One only).
3. The quotations in sealed cover shall be addressed to the Executive Engineer (City), Shivshahi Punarvasan Prakalp Ltd., Griha Nirman Bhavan, Bandra (East), Mumbai- 400 051. The blank quotations can be downloaded from the tender section of SPPL website www.sppl.biz from **01/08/2016 to 12/08/2016 upto 2.00 p.m.**
4. The quotationer shall quote in ink his percentage offer above/below or at par the estimated cost both in figures and words. The quotation should be submitted in a single sealed Envelope containing forwarding letter, quotation notice and duly filled Schedule-B and signed on each page.
5. The name of work for which quotations have been given should be stated clearly on the envelope containing the quotation and name of Contractor should be written on lower left of envelope.
6. The sealed quotation will be received by the office of Executive Engineer (City)/SPPL, 5th floor, Griha Nirman Bhavan, Bandra (East), Mumbai – 400 051 upto **3.00 p.m. by 12/08/2016** and will be opened at **3.30 p.m.** on the same day as far as possible in the presence of the contractors/their representatives whosoever remain present at that time.
7. The quantities as shown in Schedule 'B' are approximate. The payment will be made as per actual quantity of work done.
8. The acceptance of quotation shall rest with the competent authority who reserves the right to reject any or all the quotations without assigning any reason for doing so.
9. The quotation submitted by the quotationer shall be binding on him for a period of 90 days from the last date of receipt of quotation.
10. No alternation in the form of quotation or schedule of quantities, specifications shall be entertained.
11. The entire work is to be completed within **180 days**.
12. The work shall be carried out in accordance with I.S. specifications for the particular items and as per the detailed specifications mentioned in Schedule-B.

13. The rates quoted shall be inclusive of all taxes, Octroi Duty and free delivery at site of work and nothing extra shall be paid on any account.
14. The quotationer is advised to visit and examine the site of work and its surroundings before quoting the rate and acquaint themselves with the site conditions.
15. The contractor will have to make his/ their own arrangement at his/their cost for office and stores and safeguard the materials brought on the work and the materials issued by the department if any.
16. The contractor shall provide all labors, tools, pegs, watering and all other materials as required for line out and setting out the layout etc. for the work without claiming any payment.
17. After the completion of the work, the contractor shall remove forthwith all his/ their serviceable and un-serviceable materials from site of work and other debris shall be dumped and leveled as ordered within the scope of work if so ordered without any extra cost.
18. No escalation shall be paid to the contractor.
19. The successful quotationer shall have to enter into A-1 Agreement with the Executive Engineer (City)/SPPL as per the rules in force.


Executive Engineer (City),
Shivshahi Punarvasan Prakalp Ltd.
Mumbai- 400 051.

No. SPPL/ GM(Engg)/EE(City)/1080/2016,
Office of the Executive Engineer
Shivshahi Punarvasan Prakalp Ltd.
Griha Nirman Bhavan, Bandra (E),
Mumbai- 400 051.

Date : 01 / 08 / 2016

Issued to :

M/s. _____

Copy submitted to G.M. (Finance)/SPPL for information.

Copy submitted to Dy.CE/SPPL for information.

Copy f.w.c's to Accounts Officer/SPPL for information.

Copy to D.E./SPPL for information & necessary action

Copy to Notice Board/SPPL.

✓ Copy to M/s. IMPAQ TECHNOLOGIES PVT. LTD. for publishing quotation notice along with Schedule-B on SPPL website

NAME OF WORK : S.R. Scheme at Rahul Nagar, Sewri, Mumbai.

Preparation of ground for raising lawn, plantation of grass and maintenance of garden (RG1) & RG2(pt).

: SCHEDULE 'B' :								
Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount	
				In Figure	In words			
1	Bd/A-1, P.259 (It.1(a), Pg.5, PWD DSR 2015-16)	11.48	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum including removing the excavated materials upto a distance of 50 meters beyond the building area and lift upto 1.50 metres, stacking and spreading as directed including dewatering unless provided elsewhere, preparing the bed for the foundation and necessary backfilling, ramming, watering complete excluding shoring and strutting.	239.00	Rupees Two hundred thirty nine only.	Cu.Mt.	2743.72	
2	(It.3, Pg.6, PWD Parks & Garden Schedule 2012-13)	122.57	Preparing instant Lawn : Excavating the ground to a required depth of 20 cms, removing & conveying unwanted stuff to a required distance as directed, Filling fresh garden soil/silt & manure in excavated area in 3:1 proportion to a height of 20 cms, Mixing garden soil and manure thoroughly well, levelling, watering on previous hight. Planting required variety of lawn grass as directed and maintaining till well established by watering, weeding, clipping, rolling, etc. complete.	679.00	Rupees Six hundred seventy nine only.	Sq.Mt.	83225.03	
3	Bd/A-12, P.264 (It.10, Pg.7, PWD DSR 2015-16)	5.80	Providing dry trap / rubble stone soling 15cm to 20cm thick including hand packing and compacting etc. complete.	915.00	Rupees Nine hundred fifteen only.	Cu.Mt.	5307.00	
4	Bd/E-1, P-287 (It. 1c), Pg-13, PWD DSR 15-16)	2.52	Providing and laying in position in suit plain cement concrete M-10 with minimum cement content of 220 Kg./Cum. as per IS 456-2000 for foundation and bedding including admistures to accelerate, retard setting of concrete improve workability without imparing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vidrator and curing (Excluding reinforcement) etc. complete.	6018.00	Rupees Six thousand eighteen only.	Cu.Mt.	15165.36	
5	Item Code RW-3-17, Pg.7, (MCGM's Schedule for Road Works 2013)	25.22	Providing & fixing in the footpath, 60 mm thick Lacquer coated (Reflective) interlocking gray cement concrete pavers in red (Terra Cotta) Black, Brown, Lemon Yellow or any colour with vermeticular or any antiskid texture on top surface of approved pattern/ shape and colour having average crusting strength 40 N/mm ² manufactured in double layer precast concrete blocks. The top layer of paver block should be 12 to 15 mm thick and consist cubical shape stone aggregate 8 mm size sieve 100% passing and retain on 4.75 mm size sieve , silica sand and with pure iron oxide ultra voilete stabilized pigment @ 5% by weight of cement and should be coated with lacquer having hard, high abrasive resistance and water repellent. The bottom layer should be 45 to 48 mm thick having 12 mm size sieve 100% passing aggregate as per technical specification placed on uniformly graded river sand cushioning of average compacted thickness 25 mm properly compacted with mechanical compactor with required level, grade and camber etc. complete as specified and as directed by the Engineer.	938.00	Rupees Nine hundred thirty eight only.	Sq.Mt.	23656.36	

Item No.	Std. Specification	Quantity	Description	Rate		Unit	Amount
				In Figure	In words		
6	(It.Y (b)(2), Pg.16, MCGM Garden Work Schedule 2011-12)	612.85	Maintaining the lawn by watering at the rate of 6 ltrs. / Sq.M., mowing & edging the lawn twice in a month, weeding time to time.	5.25	Rupees five point twenty five paise only.	Sq.Mt.	3217.46
7	(It.5, Pg.18, MCGM Garden Work Schedule 2011-12)	20.00	Supply of lorry with 4 labours for transporting of 10 Cu. M. capacity for 1 shift.	2763.00	Rupees Two thousand seven hundred sixty three only.	Shift	55260.00
8	Bd/E-2, P-288 (It. 4, Pg-14, PWD DSR 15-16)	0.13	Providing and casting in situ plain cement concrete M-15 grade with minimum cement content 320 Kg/Cum. As per approved mix design as per BIS 456-2000 by Engineer -in-charge for bed blocks, foundation blocks and such other items including admixtures to accelerate, retard setting of concrete to improve workability without impairing strength and durability. The rates shall includes bailing out water manually centering, shuttering, compacting by vibrator and curing (Excluding reinforcement) etc. complete.	6882.00	Rupees Six thousand eight hundred eighty two only.	Cu.Mt.	894.66
9	As per wording of Item (Rate Analysis)	4.00	Providing and fixing VIP Bench of Arihant Industrial Corporation Limited with their drawings and specifications and as per Item Code no. PGGD22 etc. complete.	24553.00	Rupees Twenty four thousand five hundred fifty three only.	Per Bench	98212.00
Total Rs.							287,681.59
Say Rs.							287,682.00

(Rupees Two Lakhs Eighty Seven thousand Six Hundred Eighty Two only)

I/We hereby agree to quote _____% Above/Below or At par with the estimated cost put to the tender.

Therefore, the amount (in figure) _____ (in words) _____

Signature of Contractor/s

Executive Engineer (City)/SPPL